

Scope of Work for Croyle II Well, Well House and Water Main

A. Schedule A: Croyle II Well

The Schedule A scope of work includes well drilling and setting a 100 HP well pump and drop pipe for a 1200 ft. deep Madison Aquifer well.

B. Schedule B: Croyle Well House

The Schedule B scope of work includes 24' x 30' well house structure, mechanical piping, instrumentation, electrical, controls wiring, HVAC systems, chemical feeds systems, automatic filter system, Multi-Media Filters, casework and related work.

C. Schedule C: Croyle Avenue Water Main, Site Work and Backwash Detention System

The Schedule C scope of work includes 2400 ft. of 8" water main, water services, fire hydrants, culverts, asphalt, erosion control, precast concrete tanks, detention chambers, restoration and related work.