

**ADDENDUM NO. 1**  
**to**  
**PROJECT SPECIFICATIONS,**  
**CONTRACT DOCUMENTS AND DRAWINGS**

PROJECT: **Yosemite Way Street and Drainage Repairs  
Whitewood, South Dakota**

OWNER: City of Whitewood, South Dakota  
1025 Meade Street  
Whitewood, SD 57793

ENGINEER: CETEC Engineering Services, Inc.  
1560 Concourse Drive  
Rapid City, SD 57703

LETTING: July 28, 2009, 10:00 A.M.

PREBID CONFERENCE: July 24, 2009, 10:00 AM , Whitewood City Hall

DATE OF THIS ADDENDUM: Friday, July 24, 2009

*Acknowledge receipt of this addendum on Page 00310.1 of Section 310 Bidders Proposal.*

SCOPE: This addendum consists of two (2) page(s), A1.1 through A1.2.

**CHANGES/CLARIFICATIONS TO PLANS AND SPECIFICATIONS:**

---

**Item      Description**

**1.1      Section 02575 – PAVEMENT REMOVAL, REPAIR AND SURFACING**

**CHANGE:** SDDOT Specifications require the use of a paver feeder (pick-up machine) for lengths greater than 500'. The use of a paver feeder will **NOT** be required.

**1.2      Section 02575, Part 2 - Products – PAVEMENT REMOVAL, REPAIR AND SURFACING**

**CLARIFICATION:** Asphalt Cement shall be either PG 58-28 or 64-22. Aggregate shall meet the requirements of Class G or E, Type 1.

**1.3      Plans, sheets 9, 10, & 12- Adjust Manhole frame and lids**

**CLARIFICATION:** extent of work required will be to adjust the manholes to ¼" below finished asphalt surface elevation. Grouting, rings, etc may be necessary. Installation of chimney seals, if none exist, is not required.

1.4 WORK RESTRICTION:

No work will be allowed on Crook City Road from August 3<sup>rd</sup> through August 9<sup>th</sup>.

CETEC Engineering Services, Inc.

By: Rich Marsh  
Rich Marsh, P.E., Project Manager

Date: 7-24-09