

## ADDENDUM NO. 1

PROJECT: **Legion Lake Campground Road Construction and Utility Relocation**

BID LETTING: September 15, 2009 at 10:00 A.M. MDT

LOCATION: CETEC Engineering Services, Inc.  
1560 Concourse Drive  
Rapid City, SD 57703

SCOPE: This Addendum consists of two pages, A1.1 – A.1.2.

ACKNOWLEDGMENT: Bidder shall acknowledge receipt of this Addendum in the Bidders Proposal form on page 14.

DATE: Monday, September 14, 2009

### CHANGES / CLARIFICATIONS / ADDITIONS TO PLANS AND SPECIFICATIONS:

---

| <u>Item</u> | <u>Description</u> |
|-------------|--------------------|
|-------------|--------------------|

|     |  |
|-----|--|
| 1.1 | Testing Requirements, Page 52, Section 9.7.1 |
|-----|--|

**ADD** to the end of Section 9.7.1:

“Owner will furnish inspection and testing. Costs associated with re-testing due to failing tests will be the responsibility of the Contractor.”

|     |  |
|-----|--|
| 1.2 | Water Mains and Appurtenances, Page 02660.3, Section 2.1 |
|-----|--|

**ADD** to the end of section 2.1.D.2

“Substitute brass compression fittings in lieu of Polypropylene fittings”

|     |               |
|-----|---------------|
| 1.3 | Plan sheet 4. |
|-----|---------------|

**ADD** Salvaging 1,686 SY gravel surfacing materials from camp pads shall be an incidental work item under bid item No. 2 Incidental Work.

**ADD** 4” topsoiling salvage and placement shall be considered Incidental Work under Bid Item No. 2.

|     |                |
|-----|----------------|
| 1.4 | Plan sheet 14. |
|-----|----------------|

**CHANGE** the note stating “Connect to existing 1” water line (field verify depth & location)” to read:

“Connect proposed 2” HDPE Water Main to existing 4” water main via 4”x2” tapping saddle. (All work associated with water main tap and saddle shall be considered incidental work, field verify depth and location)”.

CETEC Engineering Services, Inc.

By: Ted Schultz by Brian Dale  
Ted Schultz, P.E., Project Manager

Date: 9-14-09